



A45 Ersatzneubau Talbrücke Heubach

SHORT DESCRIPTION

Demolition and new construction of a 184-meter prestressed concrete bridge on the A45 between Dortmund and Giessen.

THE PROJECT

The Heubach viaduct on the A45 consists of two partial structures each, which will be replaced by a new structure. The prestressed concrete structures, including the piers and abutments, will be completely demolished and also rebuilt in prestressed concrete. In the first construction phase, the first partial structure in the direction of Hanau will be demolished and rebuilt. In the second construction phase, the second partial structure in the direction of Dortmund will be demolished and rebuilt. The demolition and new construction of the Heubach viaduct will be supported by the use of a feed scaffold. The superstructures of the freeway bridge will be built separately for each directional carriageway as continuous girders over 5 spans (32 m - 37 m - 48 m - 37 m - 30 m = 184 m). The superstructures will be constructed as longitudinally prestressed double-web slab beams in cast-in-place concrete. The continuous girder has a haunched cross-section on the two central column axes, tapering from 3.20m to 1.80m. The Heubach viaduct is scheduled for completion in April 2026.

SERVICES IN DETAIL

Concrete and reinforced concrete works, prestressed concrete works, shoring works, deep foundation works, demolition works, earthworks, road works, waterproofing works, bridge equipment, piping works, drainage works.

CHALLENGES

Demolition and new construction of the partial structures in the direction of Hanau and in the direction of Dortmund using a feed scaffold.

SUSTAINABILITY

The client has established an ecological construction supervision. In cooperation and coordination with the ecological construction supervision, far-reaching measures for the protection of flora and fauna are implemented, such as water protection through temporary piping, ant relocation, illumination of the bridge structure to protect young animals and bats.

FACTS

Location	Ehringshausen , Germany
Status	Under construction
Construction volume (value of our services)	18.5 M EUR

Start of construction	December 2021
Completion	April 2026
Building owner	Autobahn GmbH des Bundes Niederlassung Westfalen Außenstelle Dillenburg
Project management	ARGE: Techn. Federführer Implenía Construction GmbH NL Mitte und NL West 65479 Raunheim; Kaufmännische Leitung Fritz Herzog AG, 35043 Marburg
ARGE	✓

SERVICES

Road construction

Infrastructure



<https://implenia.com/en/references/detail/ref/a45-ersatzneubau-der-talbruecke-heubach/>

Creation: 03.06.2026 12:55