

# Construction of a workshop and storage building



#### **SHORT DESCRIPTION**

Construction of a workshop and storage building in 8 months. From building shell construction to painting work.

#### **THE PROJECT**

• Construction period: 8 months

## Earthwork, drainage and surface work

- Ground excavation and removal: approx. 7,600 m<sup>3</sup>
- Hard limestone material as soil replacement: approx. 2,800 m<sup>3</sup>
- Drainage pipes made from concrete, stone and PVC plastic: approx. 190 m
- Concrete paving including substructure: approx. 1,250 m<sup>2</sup>
- Angled supporting wall, height up to 4.10 m: approx. 50 running metres

## Building shell construction work:

- Formwork for various components: approx. 2,000 m<sup>2</sup>
- Concrete for various components: approx. 830 m<sup>3</sup>
- Reinforcement of various components: approx. 90 t
- Sand-lime brick as exposed brickwork: approx. 195 m<sup>3</sup>
- Sand-lime brick as faced brickwork: approx. 370 m<sup>2</sup>

## Finishing work:

- Industrial screed (magnesite screed): approx. 1,500<sup>2</sup>
- Tiling work
  - Walls approx. 60 m<sup>2</sup>
  - Flooring approx. 320 m<sup>2</sup>
- Dry construction work
  - Walls approx. 180 m<sup>2</sup>
  - Suspended ceilings approx. 320 m<sup>2</sup>
- Painting work approx. 3,300 m<sup>2</sup>

## **FACTS**

Location	Bottrop , Germany
Status	completed
Construction volume (value of our services)	860,000 EUR
Start of construction	January 2007

## **SERVICES**

Tesch
Building construction



https://implenia.com/en/references/detail/ref/construction-of-a-workshop-and-storage-building/

Creation: 14.12.2025 04:27