

Kaiseraugst Bollingerhaus



SHORT DESCRIPTION

Complete excavation of the economic part. Support and securing of the roof structure to be protected. Measures to secure the facade.

THE PROJECT

All facade walls exkl. South facade had to be preserved. Underpinning of the remaining natural stone walls. Complete integration of a new building, incl. construction of a new basement, in the area of the economy part in solid construction. Load transfer of the existing truss structures via the new concrete floor. Reconstruction of the residential part and securing of the vaulted cellar. Construction of wood-concrete composite ceilings. Creation of new insulation perimeters on the roof and walls New exterior cladding in wood

SERVICES IN DETAIL

- BKP 214 Assembly construction in wood

CHALLENGES

1700-year-old Roman fort masonry and a defense tower that came to light during the reconstruction. The preservation of the old entablature and the new load transfer in cramped conditions, without using or damaging the existing structure. Insertion of elements and implementation of fire protection requirements

FACTS

Location	Basel , Switzerland
Status	completed
Construction volume (value of our services)	580,000 CHF
Start of construction	September 2019
Completion	September 2021
Building owner	Ortsbürgergemeinde Kaiseraugst, 4303 Kaiseraugst
Architect	Architects AG, 5080 Laufenburg
Heating-ventilation-air-conditioning-sanitary (HVACS) planner	Engineers AG, 5070 Frick

SERVICES

Timber construction



<https://implenia.com/en/references/detail/ref/kaiseraugst-bollingerhaus/>

Creation: 11.07.2026 04:53