Implenia

Reference

Rv. 36 Skyggestein–Skjelbredstrand



SHORT DESCRIPTION

Rv. 36 Skyggestein - Skjelbredstrand is part of Bypakke Grenland Phase 1. The project is the largest single project in Bypakke Grenland together with fv. 32 Gimlevegen - Augestadvegen.

THE PROJECT

The project included 3.5 km of new 3-lane road, 1.6 km of upgrades to the existing road, and a new pedestrian and bicycle path. In addition, the project included eight concrete structures - including three bridges, two environmental culverts and a culvert for pedestrian and bicycle paths, and two stream culverts. Two traffic circles were also constructed, 2 T-intersections and 1 X-intersection. In addition, minor modifications and adjustments were made to the existing road network.

FACTS

Location	Skien, Telemark , Norway
Status	completed
Construction volume (value of our services)	325 M NOK
Start of construction	January 2017
Completion	June 2019

SERVICES

Tunnelling

https://implenia.com/en/references/detail/ref/rv-36-skyggestein-skjelbredstrand/

Creation: 02.11.2026 22:05