

Südwestumfahrung Brugg



SHORT DESCRIPTION

The new bypass will connect the lower Aare valley with the A1 and A3 motorways and provide access to Brugg/Windisch.

THE PROJECT

The Brugg south-west bypass project consists of three sub-projects, the new construction of the south branch of the K128, the new construction of the west branch of the K128 and the new construction of the connecting link K401. This new bypass will connect the lower Aare valley with the A1 and A3 motorways and provide access to Brugg/Windisch. Within this project, a complete two-lane road construction with two concrete roundabouts including various works and drainage lines was realised. Various concrete retaining walls with noise protection elements, bridge renovations and new bridge constructions, renewal and renovation of level crossings and compensation measures round off the complex overall structure.

SERVICES IN DETAIL

- Utility cable blocks VT: 3'300 m
- Service line blocks EW/water/gas: 5'000 m

• Sewerage/Drainage: 3'250 m various sizes and combinations

Stone baskets: 1'250 pcs.Retaining walls: 1'365 m

• Noise protection elements: 240 pcs

• In-situ concrete: 8'300 m³

Nail wall: 1'250 m²
Anchors: 220 pcs

• Excavation: 250'000 m³

• Pavement demolition: 25'000 m²

• Backfill/fill: 60'000 m3

• Foundation layers: 40'000 m³

Asphalt: 21'000 tonsEdge finishes: 2'000 m

• Concrete pavements: 2'850 m²

CHALLENGES

The biggest challenge was to shorten the construction time by one year during the course of the project, which was an enormous coordination effort and feat of strength. Thanks to project optimisations, bundling and cooperation of various departments and specialities from the Civil sector, we were able to present our professional competence and clout impressively and successfully.

Thanks to Circular Economy, we were also able to demonstrate how construction and resource conservation can be brought into harmony.

SUSTAINABILITY

Circular Economy

FURTHER INFORMATION

To the News

FACTS

Location	Brugg/Windisch/Hausen , Switzerland
Status	completed
Construction volume (value of our services)	33 M CHF
Start of construction	April 2019
Completion	October 2021
Building owner	Departement Bau, Verkehr und Umwelt
Project management	Alexander Stritt, Klaus Theismann
Construction management	Ingenieurgemeinschaft SWU-B-W Eichenberger AG, Gerber + Partner AG
Construction management	Ingenieurgemeinschaft SWU-B-W Eichenberger AG, Gerber + Partner AG

SERVICES

Road construction

Earthworks

Stabilisation

Construction of drains and service lines

Concrete surfaces: roads

Road and surface construction

Urban transport infrastructure



https://implenia.com/en/references/detail/ref/suedwestumfahrung-brugg/

Creation: 02.01.2026 16:17