Umgestaltung Worbstrasse





SHORT DESCRIPTION

The project comprised the rehabilitation and extension of Worbstrasse between the junction with Allmendingenweg and the end of the village.

THE PROJECT

A multipurpose lane was added to the roadway to facilitate turning. The sidewalk on the Siloah side was shifted slightly towards the south. In the area of the new sidewalk and the road, the foundation layer was renewed or supplemented and all edge trims and manhole covers were replaced. The resurfacing was carried out over the entire roadway and sidewalk. Since all the work was carried out under traffic conditions, it was divided into several stages.

In addition, the platform at the RBS Siloah station was raised in order to ensure disabled access in the direction of Worb. In order not to disrupt the train schedule, this work was carried out at night.

SERVICES IN DETAIL

- Road construction
- Pavement construction
- Earthworks
- Sewer construction
- Construction of utility lines
- In-situ concrete construction

CHALLENGES

- Tight space conditions
- Adherence to schedule
- Work under heavy traffic
- Execution of the work in several stages
- Coordination between preparatory work and pavement installation
- Night work (platform construction)

FURTHER INFORMATION

Execution as sole contractor

Implenia Switzerland Ltd, Construction Switzerland CH-3007 Berne

FACTS

Location	Gümligen , Switzerland
Status	completed
Construction volume (value of our services)	1.55 M CHF
Start of construction	June 2019
Completion	June 2020
Building owner	Tiefbauamt des Kantons Bern, Regionalverkehr Bern-Solothurn RBS, BKW AG
Civil engineer	smt ag ingenieure + planer

SERVICES

Road construction

Infrastructure

https://implenia.com/en/references/detail/ref/umgestaltung-worbstrasse/

Creation: 03.11.2026 16:01